Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
4	Burnt stone slabs 6" thick neatly dressed and laid in cement mortar (1 : 6)	S.ft.	0 10 0	41	
5	Fixing C. I. shutters for distribution channel as per design complete	"	0 8 0	12	
6	Cement plastering ½" thick (1 : 3) proportion for baffle walls including "pudlo" water-proof compound ..	Sqr.	8 0 0	6 46	
7	Fixing alum mixing device at site as per specification and as per details to be worked out later on during execution	L. S.			
	III. Improvements to distribution.				
1a	Laying 7" ϕ C. I. pipes 12' long including necessary earthwork and making lead joints as per specification, etc., complete	Joint	3 12 0	31	
1b	Making lead joints for specials such as tees and bends including necessary earthwork and laying in position, etc., complete :—				
	9" ϕ	Joint	4 4 0	2	
	7" diameter	"	3 4 0	2	
	6" diameter	"	2 12 0	2	
	5" diameter	"	2 8 0	2	
	4" diameter	"	1 12 0	2	
	3" diameter	"	1 8 0	2	
2	Fixing 7" sluice valve including flange joining, etc., complete	No.	2 0 0	3	
	Alternative items that may be found necessary consistent with charges that may be made during execution.				
1	Burnt stone jelly concrete in cement mortar (1 : 6) proportion, laid in 4" layers well tamped	C.ft.	0 6 6		
2	Do do (1 : 3) proportion	"	0 10 0		
3	Casting cement concrete coping slabs (1 : 3 : 6) and finished smooth with cement plasters, etc.	C.ft.	0 12 0		
4	Laying 9" ϕ and 12' long C. I. pipes including earth work and lead jointing, etc., complete	Joint	4 12 0		
5	Do do 6" ϕ & 12' long	"	3 4 0		
6	Do do 5" ϕ & "	"	3 0 0		
7	Do do 4" ϕ & "	"	2 4 0		
8	Fixing 6" ϕ sluice valves including flange jointing, etc., complete	Each	2 0 0		
9	Do do 3" ϕ sluice	"	1 0 0		
10	Burnt brick in cement mortar (1 : 6) proportion	C.ft.	0 5 6		

C. NARAYANASAMI SETTY,
For *Executive Engineer.*

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Notification No. 14 *of* 1939-40, *dated 4th April* 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, up to 2 P.M. on the 25th April 1940, for constructing three temporary cooly sheds on the Cattle Breeding Station, Hunsur.

2. An approximate estimate of quantities for the above work is given below. The quantities are not guaranteed. The work should be completed within one month from the date of acceptance of the tender.

3. Earnest money of Rs. 60 in cash should be remitted under Revenue Deposits, at the State Huzur Treasury, Bangalore, or Hunsur Taluk Treasury, with a chellan duly filled in by the tenderer.

The tender should be superscribed "Tender for constructing three temporary cooly sheds on the Cattle Breeding Station, Hunsur." The tenders will be opened at 2-30 P.M. on 25th April 1940.

4. Subject to the formal sanction of the Director of Agriculture, the acceptance of tender rests with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be required to furnish a cash security of 5 per cent of the value of the work and to execute the usual contract bond, in default of which his tender will be considered as cancelled and the security deposit forfeited.

6. The name of the successful competitor whose tender has been accepted will be notified in due course.

7. After the acceptance of the successful tender, the earnest money deposited on the refused tenders will be arranged to be returned to the parties.

8. Rates once tendered, will on no account, be enhanced.

9. Quotations must be written in words as well as in figures.

10. The measurements checked by the Agricultural Engineer, will have to be accepted as final.

Statement showing the approximate quantity of work.

Constructing three temporary cooly sheds on the Cattle Breeding Station, Hunsur.

No.	Items of work	Unit	Quantity
1	Earthwork excavation for foundation	C.yd.	7
2	Rough stone in mud	C.ft.	174
3	Mud walls	,,	1,334
4	Plastering with mud and white-washing	Sqr.	18.0
5	Plastering with mud and cement wash	Sqr.	10.0
6	Door with teakwood frame and jungle-wood shutters	S.ft.	72
7	Windows with teakwood frame and jungle-wood shutters	,,	36
8	Pointing with cement	Sqr.	1.1
9	Flooring with gravel	,,	67
10	Jungle wood wrought and put up	R.ft.	680
11	Roofing with grass on cocoanut thatch over bamboo rafters	Sqr.	14·6
12	Painting	L. S.	
13	Tarring wood work	Sqr.	11.2

M. G. SINGARACHAR,
Agricultural Engineer.

OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, BANGALORE CIRCLE, SESHADRI ROAD, BANGALORE.

Notification No. I—39-40, *dated 9th April* 1940.

In inviting attention to notification, dated 1st March 1940, regarding the auction sale of Mango Crop belonging to Ramakrishna Krishi Shala, the public are hereby informed that the auction sale is postponed to 3rd May 1940, and intending bidders may bid for the same at the auction, which will be held in front of the Agricultural Sub-depot, Anekal, at 2 P.M.

B. DASAPPA,
Assistant Director.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT PRINTING IN MYSORE, BANGALORE.

Notice, dated 10th April 1940.

The articles noted below will be sold by public auction at the Government Central Press Premises, Bangalore, by the Superintendent, Government Printing, Bangalore, or his authorised representative on Monday the 29th April 1940, commencing at 2 P.M.

2. The highest bidder will be the purchaser. But if proper bids are not forthcoming, the articles will not be knocked down. The purchase value of the articles should be paid immediately after the sale is effected, failing which, the articles will be resold at the risk of the original purchaser who shall make good the loss if any, between the original price and the sum realised by the second sale, but shall not participate in the profit, if any.